

**SRI DHARBARANYESWARASWAMY DEVASTHANAM
THIRUNALLAR**

No. EO(T)/B1/SDSD/TNR/2022-23/ 468

Dt.: 27.09.2022

QUOTATION NOTICE

Sealed quotations are hereby invited by the Executive Officer (Temples), Sri Dharbaranyeswaraswamy Devasthanam, Thirunallar, Karaikal from the Govt contractor/ contractor who have well experienced in this field and capable for doing this work of "Providing and fixing aluminium partition, ACP sheet false ceiling, MS checkered plate flooring and setting up of computer table for Ticket counter at Sri Dharbaranyeswaraswamy Temple, Thirunallar."


The quotation will be received upto 3.30 PM and opened at 4.00 PM on **07.10.2022**. The quotation will be enclosed with Earnest Money Deposit for an amount of Rs.5,000/- (Rupees Five Thousand only) in the form of deposit at call receipt of a Nationalized / Scheduled bank or Demand draft from any Nationalized / scheduled bank in the name of "The Executive Officer (Temples), Sri Dharbaranyeswaraswamy Devasthanam, Thirunallar". Otherwise the quotation will not be considered.

Sl. No.	Description of Items	Approximate quantity required.	Rate per square feet in rupees		Amount in Rupees
			in Figure	in Words	
1	Providing and fixing ELECTRO COATING PAINTED aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS : 733 and IS : 1285, fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for fixing 4mm thick ACP Sheet and 4mm thick glass (Total height of partition 8 feet . out of this 3'6" ACP sheet balance glass work) in panelling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings- Anodized aluminium (anodized transparent or dyed to required shade according to IS : 1868, Minimum anodic coating of grade AC 15). The aluminium partition is to be provided for a size of 12 feet x 8 feet - 2 numbers and 13.5 feet x 8 feet - 2 number with necessary door arrangements fixed in the stone flooring.. The rate inclusive of all aluminium materials, ACP sheet, 4mm thick glass with ticket counter openings, aluminium but hinges, tower bolt, sliding door bolts, door stopper, handles lock and key provision and others etc., fixing charges, labour charges etc., all complete as directed by the Engineer-in-charge.	408.00 sq.foot			

2	Providing and fixing 4mm thick ACP sheet false ceiling work for a size of 12 feet x 13.5 feet. The rate inclusive of all aluminium electro painting materials, ACP sheet, and others etc., fixing charges, labour charges etc., all complete as directed by the Engineer-in-charge.	162.00 Sq.foot			
3	Providing and fixing wooden 10mm thick checkered plate platform flooring work for a size of 12 feet x 13.5 feet with GI angle flats support for a height of 1.0feet. The rate inclusive of all angles, flats checkered plate materials and others etc., fixing charges, welding charges labour charges painting charges etc., all complete as directed by the Engineer-in-charge.	162.00 Sq.foot			
4	Providing and fixing computer table for a size of 14 feet x 1 ½ feet using 12 mm thick pre-laminated particle board with aluminum channel support. The rate inclusive of all steel materials, 12 mm thick pre-laminated particle board and others etc., fixing charges, labour charges etc., all complete as directed by the Engineer-in-charge.	1.00 No.			

Conditions:

1. No advance payment will be made
2. The work shall be completed within fifteen days from the receipt of work order.
3. The quoted amount includes GST and all taxes and I.T @ 1% (Individual) or 2% (Firm) will be deducted from the bill value.
4. Payment will be released only after satisfactory completion of work.
5. The undersigned reserves the right to accept or reject any or all of the quotations without assigning any reasons thereof.


(K. ARUNAGIRINATHAN)
EXECUTIVE OFFICER (TEMPLES)

Office Notice Board:-

- 1) The District Collector, Karaikal
- 2) The Superintending Engineer, Circle-III, PWD, Karaikal.
- 3) The Executive Engineer, B&R Division, P.W.D., Karaikal.
- 4) The Executive Engineer, I&PH Division, P.W.D., Karaikal.
- 5) The Commissioner, Municipality, Karaikal.
- 6) The Assistant Engineer (Planning), Circle III, PWD, Karaikal.
- 7) The Secretary, Arasu Oppantha Karargal Sangam, 55 Sriram Nagar, Karaikal.
- 8) The Builders Association of India, Karaikal Centre, No.47, 1st Floor, Oppilamaniar Koil Street (Near CSC Computer Centre), Karaikal.
- 9) The Puducherry and Karaikal Government Contractors Welfare Association, No.88, Neduntheru, Dharmapuram, Karaikal
- 10) Karaikal District Government Contractors Association, No.38, 4th Cross, Nethaji Nagar, Karaikal
- 11) Arulmighu Badrakaliyamman Devasthanam, Ambagarathur.
- 12) Temple web site
- 13) Spare copy.