

**GOVERNEMENT OF PUDUCHERRY**  
**DEPARTMENT OF HINDU RELIGIOUS INSTITUTIONS**  
**OFFICE OF THE EXECUTIVE OFFICER (TEMPLES)**  
**SRI DHARBARANYESWARASWAMY DEVASTHANAM**  
**THIRUNALLAR**

No.: EO(T)/B2/SDSD/TNR/2023-24/662

Dt.: 13.11.2023

**Re - QUOTATION NOTICE**

Sealed quotations are hereby invited by the undersigned on behalf of Sri Dharbaranyeswara swamy Devasthanam, Thirunallar from the Government registered Contractor / firm who are having Experience in this field for the work of “**Electrical wiring works to the existing shed at Nalavinayager Temple and North Madavelagm belongs to Sri Dharbaranyeswaraswamy Devasthanam, Thirunallar.**”

The quotation will be **received up to 3.30 PM and opened at 4.00 PM on 21.11.2023**. The quotation will be enclosed with Earnest Money Deposit for an amount of **Rs. 5,000/- (Rupees Five Thousand only)** in the form of deposit at call receipt of a Nationalized / Scheduled bank or Demand draft from any Nationalized / scheduled bank in the name of “The Executive Officer (Temples), Sri Dharbaranyeswaraswamy Devasthanam, Thirunallar”. Otherwise the quotation will not be considered.

Sl. No.	Description of Items	Approximate Quantity	Unit	Rate in rupees per unit		Amount in Rupees
				in Figure	in Words	
(1)	(2)	(3)	(4)	(5)	(6)	(7)
1	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in existing MS roofing and binding with copper wire, making good the same in case of recessed conduit as required - 20mm (Non PSR)	150.00 Rum	1 Rum (One Running Meter)			
2	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in existing MS roofing and binding with copper wire, making good the same in case of recessed conduit as required - 25mm(Non PSR)	250.00 Rum	1 Rum (One Running Meter)			
3	Supplying and fixing PVC batten / angle holder including connection etc. as required. (1.58)	25.00 Nos.	1 No. (One Number)			
4	Supplying and fixing PVC 20 mm junction box , one way (1216)	30.00 Nos.	1 No. (One Number)			
5	Supplying and fixing PVC 20 mm junction box , two way (1217)	25.00 Nos.	1 No. (One Number)			
6	Supplying and drawing following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface / recessed steel / PVC conduit as required - 1 X 1.5 sq.mm. (code 1.17.1)	350.00 Rum	1 Rum (One Running Meter)			
7	Supplying and drawing following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface / recessed steel / PVC conduit as required -2 x 2.5 sq.mm. (code 1.17.11)	550.00 Rum	1 Rum (One Running Meter)			
8	Supplying and drawing following sizes of FRLS PVC insulated copper conductor single core cable in the existing surface / recessed steel / PVC conduit as required -3 x 2.5 sq.mm (code 1.17.12)	150.00 Rum	1 Rum (One Running Meter)			
9	Supplying and fixing following modular switch / socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required - 5/6 A switch. ( code 1.24.1)	20.00 Nos.	1 No. (One Number)			
7.	Supplying and fixing following modular switch / socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required - 3 pin 5/6 A socket outlet. ( code 1.24.4)	6.00 Nos.	1 No. (One Number)			

(1)	(2)	(3)	(4)	(5)	(6)	(7)
8.	Supplying and fixing following size / modules, GI box along with modular base & cover plate for modular switches in recess etc. as required - 12 module (125mm x 125mm.) ( code 1.27.6)	6.00 Nos.	1 No. (One Number)			
9.	Supplying and fixing following Modular base & cover plate on existing modular metal boxes etc.as required - 12 module code. (1.28.6)	6.00 Nos.	1 No. (One Number)			
10.	Supplying and fixing 3 pin, 5 A ceiling rose on the existing junction box / wooden block including connection etc as required. ( code 1.33)	25.00 Nos.	1 No. (One Number)			
11.	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface / recess, complete with tinned copper bus bar , neutral bus bar, earth bar, din bar, inter- connections, powder painted including earthing etc. as required (But without MCB / RCCB / Isolator) - 6 way , double door (code 2.3.1)	3.00 No.	1 No. (One Number)			
12.	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10kA, "C" curve , miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc .as required. - Single Pole. (code 2.10.1)	18.00 Nos.	1 No. (One Number)			
13.	Supplying and fixing of 20W single LED tube light with fitting. Make: Philips/ Havells.. <u>.(Non PSR)</u>	30.00 Nos.	1 No. (One Number)			
14.	Supplying and fixing of copper wire 8SWG (4.6mm dia) for earthing arrangement including GI pipe, bolt and nuts. <u>.(Non PSR)</u>	2.00 No.	1 No. (One Number)			
15.	Supplying and fixing of 45W LED bulb (Pin Type) with fitting.(Rocket Bulb) Make: Syska / Crompton <u>.(Non PSR)</u>	25.00 Nos.	1 No. (One Number)			
16.	Supplying and fixing of Aluminium bulb shade for hanging light outdoor large type. <u>.(Non PSR)</u>	20.00 Nos.	1 No. (One Number)			

**Conditions:**

1. No advance payment will be made.
2. The validity of the quotation shall be 60 (**Sixty**) days.
3. The work shall be completed within fifteen days from the receipt of work order.
4. The quoted amount shall include GST and all taxes and I.T @ 1% (Individual) or 2% (Firm) and the same will be deducted from the bill value.
5. Payment will be released only after satisfactory completion of work.
6. The successful bidder shall bound to execute upto 30% (+) plus or (-) minus in the schedule quantity of quotation, if necessary during the execution of work at the quoted rate.
7. The undersigned reserves the right to accept or reject any or all of the quotations without assigning any reasons thereof.



(K.ARUNAGIRINATHAN)  
EXECUTIVEOFFICER (TEMPLES)

**Office Notice Board:**

1. The Collector, Karaikal cum Special Officer, Sri Dharbaranyeswaraswamy Devasthanam, Thirunallar
2. The Superintending Engineer, Circle III, Public Works Department, Karaikal.
3. The Executive Engineer, B & R, Public Works Department, Karaikal.
4. The Executive Engineer, I&PH, Public Works Department, Karaikal.
5. The Executive Engineer, TTTDP, Public Works Department, Karaikal.
6. The Executive Engineer, Electricity Department, Karaikal.
7. The Assistant Engineer (Planning), Circle III, Public Works Department, Karaikal.
8. The Assistant Engineer, Electricity Department, Sub Station, Pillaiteruvasal, Karaikal
9. The Additional Director, Information and Publicity, Karaikal.
10. The Commissioner, Karaikal Municipality, Karaikal.
11. The Commissioner, Commune Panchayat, Thirunallar / Nedungadu / Kottucherry / T.R.Pattinam / Neravy.
12. Sri Badrakaliamman Devasthanam, Ambagaratur.
13. Spare Copy.
14. Notice Board.